

SINGLE-LINE DIAGRAM SCHEDULE - SUBSTATION-04

Drawing Reference: E-SLD-004-REV1 | Facility: Zone 4

Equipment Tag	Description / Function	Rating / Capacity	Protection Relay
XFRM-01	Step-Down Power Transformer Unit 1	50 MVA, 132kV/33kV	SEL-787 Differential
CB-132-B1	SF6 Main Circuit Breaker 1	1700A Continuous	SEL-751 Overcurrent
CB-132-C1	SF6 Main Circuit Breaker 2	1900A Continuous	SEL-751 Overcurrent

Total Operational Transformer Count for SUBSTATION-04: **1 units** rated at **50 MVA**.